

केन्द्रीय रेशम उत्पादन अनुसंधान एवं प्रशिक्षण संस्थान

Central Sericultural Research & Training Institute

[केन्द्रीय रेशम बोर्ड -

वस्त्र मंत्रालय - □ □]

मानंदवाडी रोड, श्रीरामपुरा,



[Central Silk Board -

Min. Of Textiles - Govt. of India]

Manandavadi Road, Srirampura

मैसूर - 570 008

Mysore - 570 008

No. CSB/RTI/ROB/103/FMS/Mint-47

Date: 33.10.2026

To,
M/s

Sirs,

Sub: Inviting Sealed quotations for Construction of a shed for storage of tractor-mounted heavy implements under Farm Management Section of this institute - reg

=X=X=X=X=X=

It is to inform that the Construction of a shed for storage of tractor-mounted heavy implements under Farm Management Section of this institute. Hence, sealed quotations is invited from the reputed Licensed/Registered/GST holder suppliers/civil contractors/agencies to submit their lowest rate as per specification detailed below:-

Sl No	Descriptions of goods area and Specifications.	Nos	Unit	Qty	Particular amount in Rs.	Total Amount	Remark
01.	Earth Work in Excavation						
	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches Foundation of Buildings & bridges and such similar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work. In all kinds of soils Depth upto 1.5 m	1	m3	19.01			
02.	PCC						
	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenance required to complete the work as per technical specifications. i: Mix 1:4:8 Using 40 mm nominal size graded crushed coarse aggregates	1	m3	10.92			

दूरभाष/Telephone: 0821-2362440 निदेशक/Director: 2362757 फैक्स/Fax: 2362845 वेबसाईट/Web : www.csrtimys.res.in



csrtimys



csrtimys



csrtimysore

ई-मेल/E-mail : csrtimys.csb@nic.in

Central-Silk-Board

csbmot

csrtimys@gmail.com

03.	RCC						
	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all others and all the other appurtenance required to complete the work as per technical specifications. Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates m ³ 6404.00	1	m3				
04.	Footing	1	m3	1.20			
	Pedestal	1	m3	1.46			
	Raft Slab	1	m3	7.50			
05.	Masonry Work(6" Block Work)						
	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m ³ and minimum compressive strength of 4.00 N/mm ² conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	1	Sqm	30			
06.	Plastering Works						
	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix :1:6 (1 cement: 6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	1	Sqm	63.93			

07.	TMT Steel						
	Supplying, fitting and placing TMT FE 550/550D Steel Reinforcement complete as per drawing and technical specification and including Cutting , bending and Labour	1	Kg	280			
08.	Structural Steel						
	Providing and fixing Structural Steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-inCharge.	1	Kg	570			
09.	Roofing GI Sheet						
	Providing & fixing corrugated G.S. sheet roofing including vertical /curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete as per design drawings (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and and shape wherever required as per the direction of Engineer in charge.	1	Sqm	167.5			

[केंद्रीय रेशम बोर्ड -

वस्त्र मंत्रालय - भारत सरकार]

मानंदवाडी रोड, श्रीरामपुरा,

मैसूर - 570008.



[Central Silk Board-

Min. of Textiles - Govt. of India]

Manandavadi Road, Srirampura,

MYSORE - 570 008.

http: www.csrtimys.res.in

TERMS AND CONDITION

The sealed quotations to be addressed to the Director, CSR&TI, Mysore and on the cover it should be super scribed that " QUOTATION FOR CONSTRUCTION OF SHED FOR A SAFE STORAGE OF TRACTOR MOUNTED/ HEAVY FARM IMPLEMENTS UNDER FARM MANAGEMENT SECTION OF THIS INSTITUTE " with last date 16/11/26 at 11 AM for submission of quotation and date 16/11/26 at 3 PM of opening of quotation.

EMD	NA (Not applicable)/will not carry any interest.
EXEMPTION FROM EMD	NA (Not applicable)
VALIDITY	The rate quoted should be valid for a period of 180 days from the date of opening of the quotations
DELIVERY SCHEDULE	F.O.R. CSRTI, MYSORE
PAYMENT SCHEDULE	Payment will be effected only after satisfactory supply and its installation of item in good working conditions
TAXES/OTHER STATUTORY PAYMENTS	Should be quoted separately and DUTIES in percentage wherever applicable
WARRANTY	Should be indicated

The materials/repair supplied shall be in conformity with specifications.

The undersigned is right and reserve to accept or reject any quotation and the process in any time

The scope of work mentioned above is tentative. Contractors are advised to visit the site between 10:00 AM to 4:00 PM on working days at their own cost and obtain necessary information for preparing the quotation (location, quantum and nature of work, etc.). Payment will be made as per actual measurement and certification by the indenter/concerned officer. Concerned contractor will be responsible for actual measurement of the area & quote their rate accordingly, If any discrepancy is there in measurement they may mentioned in remarks column.

Yours faithfully,

Asst. Director (A&A)

Copy to : 1. DD Comp, CSRTI, Mysore for uploading website & CPPP Portal
2. Scientist-B, FMS section, CSRTI, Mysore for information.